

Priority Project #6

Install Sidewalk Along The Bus Loop

Findings:

- ✓ At dismissal, buses are stationed in a single file queue in a specific order
- ✓ School dismissal is at 2:20 PM and buses depart the school at 2:26 PM
- Buses are loaded simultaneously in the PM; some students must walk through grass to board bus

Recommendations:

- ✓ Install a 8 foot sidewalk around the south side of the bus loop to provide a paved connection to all bus loading areas; connect new sidewalk to CR 565A sidewalk project
- ✓ Install a stop sign at the bus loop exit

