

Priority Project #1

Restripe and update crosswalks at the two school driveways, check visibility and site distance at drop-off driveways, check visibility and site distance at drop-off

Findings / Recommendations:

- ✓ The crosswalks at the two school driveways have faded. They should be restriped with FDOT ladder style crosswalks.
- ✓ Visibility seems to be impaired by the landscaping at the drop-off / pick-up driveway - remove or reduce landscaping to improve visibility for vehicles and pedestrians
- ✓ Posted sign prohibiting bicycles should be moved to more appropriate location

