

Project Name: Wildwood Batting Cages

Jurisdiction: City of Wildwood

LEVEL OF SERVICE (LOS) - PROJECT CAPACITY INQUIRY																	
Segment ID	Roadway	Segment		Adopted LOS	Adopted Capacity	Existing PM Peak Hour/Peak Direction								V/C Ratio	Available Capacity	Project Trip Distr (%)	Project Impact (%)
		From	To			NB/EB	Project	Total	LOS	SB/WB	Project	Total	LOS				
3537130	C-466	CR 209	US 301/SR 35	D	572	211	1	212	B	379	1	380	C	0.66	192	5%	0.17%
3537140	C-466	US 301/SR 35	CR 105	D	1,960	708	6	714	B	954	5	959	B	0.49	1,001	30%	0.31%
35371401	C-466	CR 105	CR 103	D	1,960	681	5	686	B	824	6	830	B	0.42	1,130	30%	0.31%
3537150	C-466	CR 103	CR 101	D	1,960	929	10	939	B	981	12	993	B	0.51	967	60%	0.61%
40010001	CR 103	C-466 E	WOODRIDGE DR	D	1,274	81	10	91	B	101	12	113	B	0.09	1,161	60%	0.94%
400100012	CR 103	WOODRIDGE DR	CR 102	D	572	76	1	77	B	76	1	77	B	0.13	495	5%	0.17%
32533001	US 301/SR 35	C-472	C-466	D	1,960	783	1	784	B	547	1	548	B	0.40	1,176	5%	0.05%
32533101	US 301/SR 35	C-466	CR 204	D	1,960	729	4	733	B	412	3	415	B	0.37	1,227	20%	0.20%

Note: Existing Volumes are based on the Sumter County TMS Report dated January 17, 2012