

**Project Name: Compass Storage Facility**

**Jurisdiction: City of Wildwood**

LEVEL OF SERVICE (LOS) - PROJECT CAPACITY INQUIRY																						
Segment ID	Roadway	Segment		Adopted LOS	Adopted Capacity	Pk Hr/Pk Dir Volume Capacities					Existing PM Peak Hour/Peak Direction							V/C Ratio	Available Capacity	Project Trip Distr (%)	Project Impact (%)	
		From	To			A	B	C	D	E	NB/EB	Project	Total	LOS	SB/WB	Project	Total					LOS
3537140	C-466	US 301/SR 35	CR 105	D	1,960	0	1,560	1,890	1,960	1,960	894	6	900	B	982	7	989	B	0.50	971	100%	0.36%
35371401	C-466	CR 105	CR 103	D	1,960	0	1,560	1,890	1,960	1,960	727	5	732	B	905	5	910	B	0.46	1,050	75%	0.26%
32533001	US 301/SR 35	C-472	C-466	D	1,960	0	1,560	1,890	1,960	1,960	1,012	0	1,012	B	811	1	812	B	0.52	948	5%	0.05%
32533101	US 301/SR 35	C-466	CR 204	D	1,960	0	1,560	1,890	1,960	1,960	855	2	857	B	689	1	690	B	0.44	1,103	20%	0.10%

Note: Existing Volumes are based on the Sumter County TMS Report dated November 20, 2012