

LEVEL OF SERVICE (LOS) - PROJECT CAPACITY INQUIRY																						
Segment ID	Roadway	Segment		Adopted LOS	Adopted Capacity	Pk Hr/Pk Dir Volume Capacities					Existing PM Peak Hour/Peak Direction						V/C Ratio	Available Capacity	Project Trip Distr (%)	Project Impact (%)		
		From	To			A	B	C	D	E	NB/EB	Project	Total	LOS	SB/WB	Project					Total	LOS
3543100	C-472	US 301/SR 35	CR 117	D	572	0	332	533	572	572	142	3	145	B	122	2	124	B	0.25	427	4%	0.52%
3253290	US 301/SR 35	CR 222	C-472	D	1,960	0	1,560	1,890	1,960	1,960	710	9	719	B	614	9	623	B	0.37	1,241	13%	0.46%
32533001	US 301/SR 35	C-472	C-466	D	1,960	0	1,560	1,890	1,960	1,960	1,012	56	1,068	B	811	56	867	B	0.54	892	83%	2.86%

Note: Existing Volumes are based on the Sumter County TMS Report dated November 20, 2012
 Project trips were revised to reflect net trips based on 16% passby reduction.