

LEVEL OF SERVICE (LOS) - PROJECT CAPACITY INQUIRY

Segment ID	Roadway	Segment		Adopted LOS	Adopted Capacity	Pk Hr/Pk Dir Volume Capacities					Growth Rate(%)	Future PM Peak Hour/Peak Direction							V/C Ratio	Available Capacity	Project Trip Distr (%)	Project Impact (%)	
		From	To			A	B	C	D	E		NB/EB	Project	Total	LOS	SB/WB	Project	Total					LOS
3537140	C-466	US 301/SR 35	CR 105	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	930	1	931	B	1,021	4	1,025	B	0.52	935	30%	0.20%
35371401	C-466	CR 105	CR 103	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	756	3	759	B	941	12	953	B	0.49	1,007	100%	0.61%
3537150	C-466	CR 103	CR 101	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	1,100	9	1,109	B	1,123	2	1,125	B	0.57	835	70%	0.46%
3537180	C-466	CR 101	BUENA VISTA BLVD	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	1,312	9	1,321	B	1,288	2	1,290	B	0.67	639	70%	0.46%
32533001	US 301/SR 35	C-472	C-466	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	1,052	3	1,055	B	843	1	844	B	0.54	905	25%	0.15%
32533101	US 301/SR 35	C-466	CR 204	D	1,960	0	1,560	1,890	1,960	1,960	2.00%	889	0	889	B	717	1	718	B	0.45	1,071	5%	0.05%

Note: Future volumes are based on the Sumter County TMS Report dated November 20, 2012