

# Traffic Control Devices

242 North Westmont Drive  
Altamonte Springs, FL 32714

Phone: (407) 869-5300  
Fax: (407) 682-0076

<b>To:</b> Lake County	<b>Contact:</b> Denis Dietz
<b>Address:</b> 28127 CR561 Tavares, FL 32778	<b>Phone:</b> 352-742-1766
	<b>Fax:</b> 352-742-3511
<b>Project Name:</b> 223-DMH CR44A @ CR439	<b>Bid Number:</b> RFP04-113
<b>Project Location:</b> CR44A @ CR439, Lake, FL	<b>Bid Date:</b>

Item #	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
101-1	Mobilization - 5% Or Min. Or \$250.00	1.00	AMBY	\$4,268.69	\$4,268.69
Lake	MOT PI	1.00	EACH	\$300.00	\$300.00
620-1 -1	Grounding Electrodes F&I	160.00	LF	\$5.75	\$920.00
630-1-12	Conduit Underground F&I	999.00	LF	\$4.60	\$4,595.40
630-1 14	Conduit, Jacked F&I	137.00	LF	\$14.50	\$1,986.50
632-6-1	Signal Cable For (Flashing Beacon) F&I	400.00	LF	\$3.40	\$1,360.00
632-7-1	Signal Cable F&I	1.00	AMBY	\$2,735.00	\$2,735.00
634-4-112-50	Span Wire Assy. 50'-149' F&I	1.00	AMBY	\$1,056.00	\$1,056.00
634-5-1	Fiberglass Insulator F&I	20.00	LF	\$11.65	\$233.00
635-1-14	PuII Box-Non-Traff Ic Bearing F&I	20.00	EACH	\$556.00	\$11,120.00
635-1 -15	Fiber Optic Junction Box F&I	1.00	EACH	\$1,450.00	\$1,450.00
639-1 -12	Electrical Power Service, Overhead F&I	1.00	AMBY	\$498.00	\$498.00
639-2-1	Electrical Service Wire F&I	60.00	LF	\$1.50	\$90.00
641-15-44	44' Class VI Concrete Pole F&I	1.00	EACH	\$1,999.00	\$1,999.00
641-15-46	46' Class VI Concrete Pole F&I	1.00	EACH	\$2,012.00	\$2,012.00
650-1-131	Signal Head 12" Standard 3S-1 W F&I	7.00	AMBY	\$821.00	\$5,747.00
650-8-151	Signal Head 12" Light Weight 5S-1W F&I	2.00	AMBY	\$1,368.00	\$2,736.00
659-101	Signal Back Plates 3-Section F&I	2.00	AMBY	\$126.00	\$252.00
659-116	Back Plates 5 Section Cluster F&I	2.00	AMBY	\$177.00	\$354.00
660-1-109	Loop Detector Inductive Type 9 F&I	3.00	EACH	\$86.50	\$259.50
660-1-110	Loop Detector Inductive Type 10 F&I	1.00	EACH	\$125.00	\$125.00
660-2-102	Loop Assembly Type B F&I	2.00	AMBY	\$490.00	\$980.00
660-2-106	Loop Assembly Type F F&I	6.00	AMBY	\$660.00	\$3,960.00
670-5-111	8 Phase Controller Ass'y -NAZTEC With ETHERNET	1.00	AMBY	\$14,770.00	\$14,770.00
670-4-1B	Flashing Beacon Controller Assm For School AC POWERED F&I	1.00	AMBY	\$3,905.00	\$3,905.00
690-10	Remove Signal Head Assembly	9.00	EACH	\$21.00	\$189.00
630-30	Remove Concrete Strain Pole	2.00	EACH	\$1,421.00	\$2,842.00
690-50	Remove Controller Assembly	1.00	EACH	\$164.00	\$164.00
690-80	Remove Span-Wire Assembly	1.00	EACH	\$164.00	\$164.00
690-90	Remove Conduit & Cabling	1.00	EACH	\$164.00	\$164.00
699-1-1	Internally Illuminated Sign 24" X 72" F&I	4.00	AMBY	\$2,627.00	\$10,508.00
711-7	Remove Thermoplastic	326.00	LF	\$5.80	\$1,890.80
251	Symbol Single Arrow Thermo	2.00	EACH	\$95.00	\$190.00
253	24" Stop Bar Thermo	102.00	LF	\$9.25	\$943.50
700-40-1	Sign Single Post	1.00	AMBY	\$915.00	\$915.00
700-46-11	Remove Existing Sign	3.00	AMBY	\$60.00	\$180.00
700-48-18	Sign Panel	4.00	EACH	\$532.50	\$2,130.00
700-48-48	Relocate Sign Panel	2.00	EACH	\$60.00	\$120.00
700-48-60	Remove Sign Panel	2.00	EACH	\$40.00	\$80.00


Item #	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
999-1	Generator Switch Box	1.00	EACH	\$600.00	\$600.00
999-2	Generator Pad 3' X 3' X 4"	1.00	EACH	\$850.00	\$850.00
<b>Total Price for above Items:</b>					<b>\$89,642.39</b>
<b>Total Bid Price:</b>					<b>\$89,642.39</b>

**Notes:**

- All work is guaranteed to be installed in accordance with the latest applicable Code regulations, and to be free from mechanical and electrical defects for one year from the date of acceptance.
- No items quoted herein may be "broken out" without prior approval in writing.
- All survey work is to be performed by others.
- This proposal is a unit price proposal. The total sum is an approximate sum based on the estimated quantities on the attached proposal (which is an integral part of this proposal) at the unit prices depicted thereon. The final contract amount of any contract resulting from this proposal shall be based on the quantities actually installed and field verified by the Owner's architect/engineer at these unit prices.
- This proposal is per the Lake County Maintenance Contract RFP-113. Bid items 700-40-1, 700-46-11, 700-48-18, 700-48-48, 700-48-60, 999-1 & 999-2 are non-contract items.

**Payment Terms:**

Payments are to be made to us by the tenth day of the month for all work installed and materials placed on the job site during the preceding month, less five (5%) percent retainage (unless the Prime Contract calls for a different retainage percentage). Final Payment, including retainage, will be due not more than thirty (30) days after completion and acceptance of the work. Any contract resulting from this proposal shall be on the terms and conditions mutually acceptable to the Purchaser and Traffic Control Devices, Inc.

<p><b>ACCEPTED:</b> The above prices, specifications and conditions are satisfactory and hereby accepted.</p> <p>Buyer: _____</p> <p>Signature: _____</p> <p>Date of Acceptance: _____</p>	<p><b>CONFIRMED:</b> <b>Traffic Control Devices</b></p> <p>Authorized Signature: </p> <p>Estimator: Donna M. Hutchins</p>
--	--