

**City of Mount Dora**  
**Roundabout at CR 19A and Eudora Road/Old 441 Utility Relocation**  
**Bid Form**

Item #	FDOT Item #	Description	Quantity	Unit	Unit Price	Total Price
1	1050 16004	UTILITY PIPE, REMOVE AND DISPOSE, 8-19.9"	2900	LF		
2	1050 16002	UTILITY PIPE, REMOVE AND DISPOSE, 2-4.9"	750	LF		
3	1080 23104	UTILITY FIXTURE, TAPPING SADDLE/SLEEVE, FURNISH AND INSTALL, 4"	1	EA		
4	1050 31202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	70	LF		
5	1050 31204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	1082	LF		
6	1050 31208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	611	LF		
7	1050 31212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	1131	LF		
8	1050 42202	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 2"	450	LF		
9	1080 21100	UTILITY FIXTURE, VALVE/METER BOX, FURNISH AND INSTALL, 1"	5	EA		
10	1050 41201	UTILITY PIPE- POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 1"	450	LF		
11	1080 21102	UTILITY FIXTURE, VALVE/METER BOX, FURNISH AND INSTALL, 2"	6	EA		
12	1050 41202	UTILITY PIPE- POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 2"	292	LF		
13	1050 42212	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 12"	1110	LF		
14	1080 23108	UTILITY FIXTURE, TAPPING SADDLE/SLEEVE, FURNISH AND INSTALL, 8"	2	EA		
15	1080 23110	UTILITY FIXTURE, TAPPING SADDLE/SLEEVE, FURNISH AND INSTALL, 10"	2	EA		
16	1060 11211	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER, 0-80FT3, 0-6'	4	EA		
17	1060 11222	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER > 0-80FT3, 6.1-12'	4	EA		
18	1644113 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1 PUMPER, 6"	1	EA		
19	1055 51108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL ELBOW, 8"	5	EA		
20	1055 51110	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL ELBOW, 10"	3	EA		
21	1055 51112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL ELBOW, 12"	3	EA		
22	1055 51210	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL TEE, 10"	1	EA		
23	1055 51212	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL TEE, 12"	2	EA		
24	1055 51312	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH AND INSTALL REDUCER, 12"	5	EA		
25	1080 24106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	1	EA		
26	1080 24108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	2	EA		
27	1080 24110	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 10"	2	EA		
28	1080 24102	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 2"	1	EA		
<b>BID TOTAL</b>						

NOTE: PRESSURE TESTING IS INCLUDED IN THE COST OF PIPELINE INSTALLATION.