


MODIFICATION OF CONTRACT

		T	OTTHERET			
1.	Modification No.: 2	2.	Contract No.: 18-0207			
	Effective Date: 9 Oct 18		Effective Date: 25 Sep 18			
3.	Contracting Officer: B. Schwartzman	5.	Contractor Name and Address:			
	Telephone Number: (352) 343-9424		Oelrich Construction, Inc.			
4.	Issued By: Procurement Services Lake County Administration Building 315 W. Main St., Suite 441 Tavares, Florida 32778-7800	Attn: Mr. Ivan Oelrich, President 275 NW 137 <sup>th</sup> Drive Jonesville, FL 32669				
6.	modification and folding this form to affiliess shown in Brook	INSTRUCTIONS: Contractor is required to sign Block 8 showing acceptance of the below written on and return this form to address shown in Block 4 within ten (10) days after receipt. Retain a photocopy of copy of this modification and attach to original of contract, which was previously provided.				
7.						
Fully-executed Appendix K GMP form is attached hereto to document BCC confirmation of the GMP value for full-site preparation at South Lake Regional Park. This is an administrative modification not requiring vendor signature. This is considered contract modification 2 with the previously executed first amendment being the first modification to the contract.						
8.	Contractor's Signature NOT REQUIRED	9.	Lake County, Florida			
	Name:		By:			
	Title:	Procurement Services Director  UDCT 18  Date				
	Date:					
			Date			
10.	Distribution:		Date			
10.			Date			

FISCAL & ADMINISTRATIVE SERVICES – DIVISION OF PROCUREMENT SERVICES P.O. BOX 7800 • 315 W. MAIN ST., TAVARES, FL 32778 • P 352.343.9839 • F 352.343.9473 Board of County Commissioners • www.lakecountyfl.gov





October 1, 2018

Barnett Schwartzman Procurement Services Director Lake County BCC, Office of Procurement Services 315 W. Main Street, Room 416 PO BOX 7800 Tavares, FL 32778-7800

Re:

RFP#18-0207 CM-At-Risk for Full Build-Out of South Lake Regional Park (SLRP)

and Max Hooks Road Improvements

Proposal for Construction Management Services

Mr. Schwartzman

Oelrich Construction, Inc. is pleased to present this Guaranteed Maximum Price (GMP) for the construction required to complete early site mobilization. This includes handling the top soil (needed for the South Lake Park Project) before mass grading starts, building storm water collection ponds, and setting erosion control measures. Please see the attached qualifications for more specific scope items.

The Guaranteed Maximum Price for this project is:

Two Million Eight Hundred Twenty Thousand Seven Hundred Sixty-Seven Dollars .... \$2,820,767.00

Please find the attached GMP breakdown, Qualifications, and Project Schedule used to generate this

We appreciate the opportunity to be a part of this project, and we look forward to its successful completion. Please feel free to contact me at any time if you have any questions.

Sincerely, Oelrich Construction, Inc.



Derek Dykes Senior Project Manager

275 NW 137th Drive Suite A Jonesville, Florida 32669 oelrichconstruction.com

352-745-7877 CGC1510579

## CONSTRUCTION DOCUMENTS



## 100% DRAWINGS - SLP PARK

		INC.
SHEET# NAME		
CV.00	COVER SHEET	DATE
SP.00	OVERALL SITE PLAN	10/05/20
SP.01-07	SITE PLAN	10/05/20
ECP.01-07	EROSION CONTROL PLAN	10/05/20
	A SECOND	10/05/20
4 4 5,0, 10 2 11.		
000/ 5		
90% Drawings - Max Hooks Road		
SHEET# NAME		The section was
		DATE
1	KEY SHEET	
3		5/31/201
5 1 7 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	TYPICAL SECTIONS	5/31/201
	PROJECT LAYOUT	The state of the s
		5/31/2018
		Action to the second
		F. 1 22 (5)
The state of the s		
1 2 3 3 3 3 3 3		
1. 1 2. 2. 2. 2. 2. 2. 2.		

# APPENDIX K AUTHORIZATION FOR CONSTRUCTION

Pursuant to Chapter 1, Article 3 and Chapter 2, Article 2 of the Agreement Between Lake County, Florida, a political subdivision of the State of Florida ("County") and Oelrich Construction, Inc. ("Construction Manager"), for the Project known as Full Build-Out of South Lake Regional Park and Max Hooks Road Phase 1 Improvements, the County and the Construction Manager hereby execute this Appendix K and further agree as set forth below.

11	and further agree as set forth below.	Training of Thereby	execute this
1.	The Construction Manager's Guaranteed Manager's Gua	Maximum Price ("GMP") proposal inclused in the second section of the second second incorporated, is according to the second second in the second seco	ding general epted by the
2.	The Construction Management Fee isTer project is to be completed on a single undinclusive pre-construction services fee must attached to this Agreement. The Manageme	not exceed the applicable fee in the init	d the GMP- ial bid sheet
3.	The Subcontracts Cost is	(\$ <u>2,333,000)</u> .00	
4.	The Estimated County's Costs, as defined to the Million Two Million Sixty Sevential The Guaranteed Maximum Price is		3, will be
5.	The Guaranteed Maximum Price is	on Dollars (\$\(\frac{2}{820}\),767).00	nd Seven Hundred
6.	The Date of Substantial Completion will be _	March 31st, 2020	
7.	This Appendix K will include the following E	xhibits (to be attached upon execution)	
	Exhibit 1: Index of Final Plans and Speci Exhibit 2: Construction Schedule Exhibit 3: Construction Manager's Project Exhibit 4: Schedule of Values Exhibit 5: Unit Prices Exhibit 6: Construction Manager's Subsection	ifications ct Team	2.7.5.6
See at Lake C ("Count	ttached signature page County, Florida ity")	Oelrich Construction, Inc. ("Construction Manager")	
Ву:		By: Ivan Oelrich	
Its:			
Date:		Its: President Date: October 2, 2018	

## BOARD OF COUNTY COMMISSIONERS LAKE COUNTY, FLORIDA

Timothy I. Sullivan, Chairman

This 11 day of October 2018

ATTEST:

Gary J Cooney, Clerk

Board of County Commissioners

of Lake County, Florida

SHAMORE STATE OF THE STATE OF T

Approved as to form and legality:

Melanie Marsh

County Attorney

		)				
Build Haul Road 11/7 ≦ 11/27	Build 11/7	Tue 11/27/18	Wed 11/7/18	.5 days	Build Haul Road 15 days	3
Chain Link Fencing	arrier Wall and Ch	Tue 11/6/18	Wed 10/31/18	days	Barrier Wall and 5 days Chain Link Fencing	12
Clearing and Grubbing	Clearing a	Tue 10/30/18	Wed 10/17/18 Tue 10/30/18	10 days	Clearing and Grubbing	3
Erosion Control Measures	Erosion Cont 10/10	Tue 10/16/18	Wed 10/10/18	5 days	Erosion Control 5 days Measures	10
10/1	•	Tue 11/27/18	Wed 10/10/18 Tue 11/27/18	35 days	Max Hooks Road	9
	75150.4	Mon 10/1/18	Mon 10/1/18	0 days		00
Retaining Wall Construction		Tue 12/10/19	Wed 11/13/19	20 days	Retaining Wall Construction	7
avation and Construction	<b>-</b>	Tue 11/12/19	Wed 11/14/18	260 days	Pond Excavation and Construction	6
Clearing and Grubbing 10/31 11/13	Clearin	Tue 11/13/18	Wed 10/31/18	10 days	Clearing and Grubbing	5
Mass Grading and Hauling	10/17	Tue 3/31/20	Wed 10/17/18	380 days	Mass Grading and Hauling	4
Top Soil Handling 10/17 10/30	Top So 10/1:	Tue 10/30/18	Wed 10/17/18	10 days	Top Soil Handling	ω
Erosion Control Measures 10/10 11/6	Erosion Contro	Tue 11/6/18	Wed 10/10/18	20 days	Erosion Control Measures	2
Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb Mar Apr May Aug Sep Oct Nov Dec Jun Feb M	Jun Jul Aug Se	Tue 3/31/20	Mon 10/1/18	392 days	South Lake Park	_
018   Qtr 3, 2018   Qtr 4, 2018   Qtr 1, 2019   Otr 2, 2019   Otr 3, 2019   Otr 4, 2019   Otr 4, 2019   Otr 5, 2019   Otr 6, 2019   Otr 7, 201	018   Qtr 3, 2018	Finish	Start	Duration	Task Name	5
South Lake Park and Max Hooks Road Improvements	1ax Hooks	Park and N	South Lake			



October 1, 2018

Re:

RFP#18-0207 CM-At-Risk for Full Build-Out of South Lake Regional Park (SLRP)

and Max Hooks Road Improvements

Oelrich Construction Project Team and List of Subcontractors

## **Oelrich Construction Team**

Senior Superintendent

Ethan Newport

Project Manager

Ryan Minton

Assistant Superintendent -

Cozart Lawrence

Project Engineer

Sean Strayer

#### List of Subcontractors

Site work- Top Soil Handling and Pond Construction -Mass Grading the entire site

Total Earth Services J. Malever Construction\*\*\*\*

\*\*\*\* - Indicates a Lake County Subcontractor

275 NW 137th Drive Suite A Jones ville, Florida 32669

pelric inconstruction.com

352-745-7877 CGC15 ₹ 0579

# South Lake Park- Early Mobilization and Top Soil Handling Oelrich Construction, Inc.

Estimate Breakdown October 1, 2018

Section   Sect	
Foreign 18 months  General Conditions  BB-31 Silework  Surveying 1 is 65,000 65	St
Separal Conditions	Tot
South Lake Park	
South Lake Park	
MOT 1 1 5 5 5,000 65,000 65,000 65,000 65,000 1 2,000	
Surveying	
Second	
1   1   1   1   1   1   1   1   1   1	
S   S   S   S   S   S   S   S   S   S	
Sill Finders of the protection	
Silf Fence   11,025   17   18   month   3.5   875,000   875,0000	
1	
Max Hooks   As Hook   As H	
Ask Hooks	
Mobilization 1 Is	
Month   1   1   1   1   1   1   1   1   1	1,386,
1   1   1   1   1   1   1   1   1   1	
1,300   if   1,500	
It flence	
Section   Sect	
Seal Cultifor Maintenance   18 month   3.0   17,904   17,904   17,904   18   15   18   18   19   19   18   18   19   19	
1   15   17,000   1	
State   Stat	
4,430 sy 24 106,320 106,320 106,320 11 48,730 48,73	
24 106,320 106,320 11 48,730 48,730	
-32B Planting and Landscaping taining wall- entire site	
ers Risk Insurance  ent and Performance Bond ral Liability Insurance  ot Confingency  1.5%	459,39
lers Risk Insurance nent and Performance Bond rad Liability Insurance 0.98%  ct Contingency 1.5%	487,287
nent and Performance Bond ral Liability Insurance 0.98%  ct Contingency 1.5%	
ct Contingency 1.5%	,333,000
1.3%	9,799 28,400
	27,642 5,000
	36,058
ral Conditons	
5.1%	439,899
10.0%	124,435
	256,433



## Total Earth Services, LLC 8470 NE 44th Drive Wildwood, FL 34785

Office: 352-415-4888

Fax: 352-300-1126

To: Address:	Oelrich Construction Inc 275 NW 137th Dr, Suite A Jonesville, FL 32669	Contact: Phone:	Derek Dykes (352) 745-7877
Project Name:	South Lake Park – Handling Top Soil and Pond Construction	Fax:	(352) 745-7878
Project Location: Addendum#:	Hwy 50 & Max Hooks Rd, Lake County, FL	Bid Number: Bid Date:	18-065.4 9/25/2018

Item Description	Estimated Quantity Unit		
1000 General Conditions	Lottinated Quantity Unit	Unit Price	TotalPric
Mobilization & Demobilization			
Maintenance Of Traffic	1.00 LS	\$65,000.00	\$65,000.0
Construction Layout / Surveying	0.00 LS	\$0.00	\$0.00
-73	1.00 LS	\$47,300.00	\$47,300.00
	Total Price for above 1000 General C	Conditions Itama:	
2220 Demolition			\$112,300.00
Clearing & Grubbing, Disposal			
	17.00 ACRE	\$2,306.00	\$39,202.00
	Total Price for above 2220D	emolition Items:	
300 Earthwork			\$39,202.00
egular Excavation	350 000 00		
arthwork / Embankment	250,000.00 CY	\$3.50	\$875,000.00
tack Block Retaining Wall With Concrete Cap	59,664.00 CY	\$3.75	\$223,740.00
	9,688.00 SF	\$33.00	\$319,704.00
	Total Price for above 2300 E	arthwork Items:	\$1,418,444.00
370 ErosionControl		_	+-,.10,444.00
lt Fence	11 024 00 15		
aintenance	11,024.00 LF 18.00 MO	\$3.0	\$33,075.00
		\$4,500.00	\$81,000.00
	Total Price for above 2370 Erosion	Control Items:	\$114,075.00

TotalBidPrice: \$1,684,021.00

ACCEPTED:	
The above prices, specifications and conditions are satisfactory and are hereby accepted.	CONFIRMED: Total Earth Services
Buyer:	
Signature:	Authorized Signature:
Date of Acceptance:	Estimator:



# Total Earth Services, LLC 8470 NE 44th Drive

Wildwood, FL 34785 Office: 352-415-4888

Fax: 352-300-1126

Address: 275 NW 137th Dr, Suite A Jonesville, FL 32669  Project Name: Max Hooks 90%  Project Location: Hwy 50 & Max Hooks Rd, Lake County, FL Addendum#: 0  Contact: Derek Dykes  Phone: (352) 745-7877  Fax: (352) 745-7878  Bid Number: 18-065.3  Bid Date: 9/25/2018	To:	Oelrich Construction Inc		- ax. 332-300-1126
Project Location: Hwy 50 & Max Hooks Rd, Lake County, FL  Addendum ## Bid Number: 18-065.3	Address:	275 NW 137th Dr, Suite A		WELL 1985
A ddendym #			Fax:	(352) 745-7878
		Hwy 50 & Max Hooks Rd, Lake County, FL 0	UK esses	555.5

Mobilization 8 D			
Mobilization & Demobilization Maintenance Of Traffic (type K barriers) Construction Layout / Surveying	1.00 LS 1.00 LS 1.00 LS	\$40,000.00 \$75,000.00 \$20,000.00	\$40,000.00 \$75,000.00
	Total Price for above 1000 Gene	ral Conditions Items:	\$20,000.00 <u>\$135,000.00</u>
Clearing & Grubbing, Disposal	1.00 LS  Total Price for above 222	\$61,342.00 ODemolition Items:	\$61,342.00 <u>\$61,342.00</u>
Maintenance Silt Fence	18.00 M 5,969 LF Total Price for above 2370 Eros	\$4,5000 \$3.0 sion Control Items:	\$81,000.00 \$17,904.00 \$98,904.00
Haul Road Temporary Asphalt	4,430 SY 4,430 SY	\$24.00 \$11.00	\$106,320.00 \$48,730.00
	Total Price for above 2720 Base and	d Paving Items:	<u>\$155,050.00</u>

Total Project for the project : \$450,296.00

#### Notes:

- MOT @ Hwy50 is for 18 months
- Erosion Control increase for additional sod at revised DRA and maintenance to to support trucking operation Earthwork quantities increased based on road details
- Storm pipe changed from A-2000 PVC to RCP, pipe footage was added
- Gravity Wall and Handrail was added These are budget numbers
- Landscaping, Sod & irrigation not included



RFP#18-0207 CM-At-Risk for Full Build-Out of South Lake Regional Park (SLRP) and Max Hooks Road Improvements- Early Site Mobilization and Top Soil Management

10/01/2018

# Qualifications, Clarifications, Inclusions, and Exclusions

### **Division 1- General Conditions**

- The estimated project construction duration will be (18) eighteen months.
- Work will be accomplished during normal work hours.
- A Builder's Risk Insurance policy and General Liability Insurance has been included.
- A Payment and Performance Bond has been included.
- Excludes connection and impact fees.
- A Building Permit has not been included.
- Includes the SJRWMD and FDOT permit as required.
- Hazardous materials removal or mitigation is not included in our price or schedule.
- Includes all required temp utilities for the project site.

## Division 32- Landscape and Hardscape

- Includes sodding all the storm water collection ponds for the entire site.
- Includes construction of the retaining walls with a concrete cap for the entire site as shown.
- Includes 3 cast in place steps at retaining walls.
- Includes guardrails at retaining walls and cast in place steps as required.

#### Division 31- Sitework

- Includes maintenance of traffic along Max Hooks Road. This includes installing a concrete TYPE K barrier wall roughly 1300 linear feet along the mobile home park to create a safe barrier between the park and haul road as discussed.
- Includes a 6-foot chain link fence at the concrete barriers to keep children from climbing over the
- Include maintenance of traffic out on State Road 50 for truck entering the highway.
- Include construction layout and surveying as required.
- Includes clearing, grubbing, excavation, and earthwork/embankment for the storm water collection pond only for the entire site.
- Includes clearing and grubbing for Max Hooks road.
- Includes erosion control maintenance and silt fence for the entire South Lake Park site and along
- Includes removing approximately 1.4 million CY from the project site. All dirt material needed from the South Lake Park and Max Hooks project will be stored and used for the project.
- Includes building a temporary haul road per the roadway specs as shown in GAI/BESH 90% drawings for Max Hooks Road dated May 31, 2018. The haul road will be placed on the roadway shift line from station line 35+00 to station 45+00 as shown on the 90% drawings by GAI/BESH

275 NW 137th Drive Jonesville, Florida 32669 oelrichconstruction.com

352-745-7877 CGC1510579



dated May 31, 2018. This shift will create a one-way paved access for the mobile home and this access road will be on top of the existing Max Hooks road. The existing Max Hooks Road will also be widened by 12 feet from station line 20+00 to station 35+00 and will be built per GAI/BESH roadway specs on the 90% drawings dated May 31, 2018. The entire stretch of the temporary haul road will consist of a 1" layer of SP-12.5 temporary asphalt to control dust.

- Includes all road maintenance of Max Hooks road as required for this project. Road maintenance will consist of street sweeping and water trucks as need to control dust and sediment along the roadway.
- Includes handling and sorting all the top soils material onsite to be stored for use on the future projects.

# Thank You For Your Time & Consideration







