

Residential Driveway Apron Permit Application 1 1 1

	1	וליו	9	4	201	7	1 h A	il-con	Day!
,	4	: مع اهار	(J)	ું ^{દ્} ય	71	40	1	سمح المحادث	
	V	30	3		ļ	ķ	200	Ą	
						,	14.4		

FLQ-RTDA		A Company			
Date: 10/23/17 Bidg Permit No.		LAKE COUNT			
Mike Neace	1068061 / 20 /	PUBLIC WORKS DEPART			
Applicant/ Name Permit Will Be Returned To:		wnship Range			
312 S. Bay Street	North County Road 44A I	Eustis, Fl. 32726			
Applicant's Street Address	House Number / Road Name				
Eustis, Fl. 32726	38410				
Applicant's City, State, Zip	Subdivision Name				
352-589-6004	Mike Neace				
Signature of Applicant Phone Number	Applicant, Please Print Name	, .			
mike@americanfamilyhomesinc.com	CBC058306				
Applicant's e-mail address	Contractor License # (Required unless built by owner)				
Driveway must be constructed in accordance with the Lak attached sketch. Applicant holds Lake County harmless frowork. Any deviation from the attached sketch must first be Please see attached minimum requirement details for specific Check one: Clay Road — No apron required — culvert pipe may Paved Road — Option 1: 6" limerock base and a concrete (3000 PSI) using 10 foot square of 6" x 6" v pavement. Culvert pipe may be required — Sod all distances where sidewalks are present or planned, the drives the state of the square of the	om all damages, claims, or injuries whe approved in writing by Lake County factions. The required — sod all disturbed are minimum 1" Type S-III Asphalt. Whire mesh placed a minimum of 10 turbed areas.	ich may result from such oblic Works Department. as. Option 2: 6"reinforced of from edge of existing			
driveway apron (at a maximum 1.5% cross slope) in compliant County Road # 7077 To be complete	efed by County Staff				
Driveway Permit Fee: \$50.00 Check/Transaction #: Permit # 157.55 Maint Area:3 Signs Permit Shall Expire One (1) Year From Date Approved Date of Final Inspection: Inspector Comments or special conditions: The design has been reviewed and upon completion sh application. The driveway shall be constructed per application of a joint (Common Spilt) driveway or a drive Building Permit, call Lake Inspection of a joint (Common Spilt) driveway or a drive Building Permit Common Spilt) driveway or a drive Building Permit Common Spilt) driveway or a drive Building Permit Common Spilt)	Date Expired: 6/19/19 ould meet the regulations and requiperoved subdivision plans if applicate County Building Services Division was not associated with a building	able. For inspection of a on at 352-343-9634. For			
Public Works Department at 352-253-6019. Submit p Tavares, FL 32778 Public Works Department					
Road Operations Division		Driveway Apron Permit Effective February 2017			



Residential Driveway Apron

	Permit Application Requirements								
	To be completed by County Staff	77.7							
	Single Family Driveway (standard A) Joint Driveway (Common/Split) (standard B) Permit Number								
∦ ∐`	Driveway apron as <u>Swale Check</u> (standard C) Piped Driveway apron (standard D) Driveway apron conforming to Grade or Swale (standard E)								
	Driveway apron with Miami Curb & Gutter (standard M) Driveway apron with Standard Curb & Gutter (standard S)								
*The applicable driveway apron standard will be included with approved permit that is sent to applicant, *									
1.	Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness. (See detail on attachment).								
2.	To conform to sidewalk requirements, subdivision construction plans are available for review in the Lake County Public Works Department located at 323 N. Sinclair Avenue in Tavares.	e							
3.	Driveways are not permitted in the radius return of an intersection. With the exception of joir driveways, driveway aprons must be 100 feet from the nearest intersecting road and 10 feet from the nearest property corner. The driveway width at the property line may not exceed 24 feet (1 feet minimum) and shall include either the standard minimum radius of 8 feet or 8 foot long by foot wide flares on either side of the driveway, for a maximum width of 32' at the edge of the roadway, Variance requests should be submitted to the Lake County Public Works Department.	n 0							
4.	Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and/or repair. If pavers are removed to facilitate Lake County and/or a utility company to perform utility installation and/or maintenance, the paver(s) used as replacements may not be able to be matched.	y							
5.	If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood. It there are no other culverts in the neighborhood, the culvert pipe shall be a minimum of 15 inches it diameter and a minimum of 30 feet in length measured from the end of mitter to the end of mitter All right-of-way must be restored to its original condition and in accordance to applicable Lak County Codes. All disturbed areas must be sodded, matching existing grass type. Applicant shall be responsible for sod until it is established.	n r.							
6.	Driveway apron slope may not exceed 14%. Variance requests should be submitted to the Lak County Public Works Department. In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% crosslope) in compliance with ADA requirements.								
7.	Driveway permit shall expire one (1) year from date approved.								

Driveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).

I have read and understand the above requirements Applicant's Signature/Date

Public Works Department Road Operations Division

8.


Residential Driveway Apron Permit Effective February 2017



DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

RESIDENTIAL DRIVEWAY



OR

1" ASPHALT WITH

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

& 6" COMPACTED SUBGRADE

* SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT—OF—WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT—OF—WAY LINE.




DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

C

RESIDENTIAL DRIVEWAY AS SWALE CHECK



SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT-OF-WAY LINE.

1" ASPHALT WITH

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

OR

6" 3,000 PSI CONCRETE
REINFORCED WITH 10-10x6"x6" MESH
& 6" COMPACTED SUBGRADE