

(1-1) (1-1) (1-1)	MINISTER AND
KE COUNTY	Permit Application 0 1 7 0 8 0 8 2 7 [Please Print or Type] AUG 2 3 2017allo WOX S DEPOSTMEN
Date: 4/23/17 Bidg Permit N	o AUG 2 3 20176LIG WORLS DEPOSITIONED
Applicant/ Name Permit Will Be Returned	,
24734 Shetland Tra Applicant's Street Address	House Number / Road Name
Applicant's City, State, 200	Subdivision Name
Signature of Applicant Phone	Number Applicant, Please Print Name
Beller burg 333 @ hath	Contractor License # (Required unless built by owner)
install a temporary construction entrance with	new driveway, modify an existing driveway to meet county requirements, or of the public rights-of-way of County maintained roads. Issuance of a driveway ty owner for zoning, land use changes, or site improvements. The owner must
attached sketch, Applicant holds Lake Count work. Any deviation from the attached sketch Please see attached minimum requirement det Check one: Clay Road – No apron required – cult Region 1: 6" limeroo	vert pipe may be required sod all disturbed areas. ok base and minimum 1" Type S-III Asphalt. Option 2: 6"reinforced te of 6" × 6" wire mesh placed a minimum of 10' from edge of existing
In areas where sidewalks are present or plat driveway apron (at a maximum 1,5% cross slo	nned, the driveway must include a minimum 4 foot wide path traversing the pe) in compliance with ADA requirements.
County Road # 3987F	To be completed by County Staff
Driveway Permit Fee: \$50.00 Check/Trans Permit# 15775 Maint Area: 7	Saction#: 5/9 %4 Date: , 11/11/17 Fee Code: PUBSV1 Build: Date Approved: 7/5/14
Permit Shall Expire One (1) Year From Dat	o Approved Date Expired:
1)	Inspector:
Comments or special conditions:	
application. The driveway shall be constructed County Building Services Division at 352-3-4. Public Works Department at 352-253-6019.	ompletion should meet the regulations and requirements as noted on this sted per approved subdivision plans it applicable. For inspection, call Lake 43-9634. For joint (Common Split) driveway inspection, call Lake County this, Post Office Box 7800, Tavares, FL 32778

Public Works Department Road Operations Division

Pai : Ono

Residential Driveway Apron Permit Effective June 2015

JUL 0 5 2018



Residential Driveway Apron Permit Application Requirements

To be completed by County Staff	District Control of the Control of t
Single Family Driveway (standard A) Joint Driveway (Common/Split) (standard B)	Permit Number
☐ Driveway apron as Swale Check (standard C) ☐ Plped Driveway apron (standard D) ☐ Driveway apron conforming to Grade or Swale (standard E)	
☐ Driveway apron with Miaml Curb & Gutter (standard M)☐ Driveway apron with Standard Curb & Gutter (standard S)	
*The applicable driveway apron standard will be included with approved p	ermit that is sent to applicant, *

- 1. Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness. (See detail on attachment).
- 2. To conform to sidewalk requirements, subdivision construction plans are available for review in the Lake County Public Works Department located at 323 N. Sinclair Avenue in Tavares.
- 3. Driveways are not permitted in the radius return of an intersection. With the exception of joint driveways, driveway aprons must be 100 feet from the nearest intersecting road and 10 feet from the nearest property corner. The driveway width at the property line may not exceed 24 feet (10 feet minimum) and shall include either the standard minimum radius of 8 feet or 8 foot long by 4 foot wide flares on either side of the driveway, for a maximum width of 32' at the edge of the roadway. Variance requests should be submitted to the Lake County Public Works Department.
- 4. Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and/or repair. If pavers are removed to facilitate Lake County and/or a utility company to perform utility installation and/or maintenance, the paver(s) used as replacements may not be able to be matched.
- 5. If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood. If there are no other culverts in the neighborhood, the culvert pipe shall be a minimum of 15 inches in diameter and a minimum of 30 feet in length measured from the end of miter to the end of miter. All right-of-way must be restored to its original condition and in accordance to applicable Lake County Codes. All disturbed areas must be sodded, matching existing grass type. Applicant shall be responsible for sod until it is established.
- 6. Driveway apron slope may not exceed 14%. Variance requests should be submitted to the Lake County Public Works Department. In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% cross slope) in compliance with ADA requirements.
- 7. Driveway permit shall expire one (1) year from date approved.
- 8. Driveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).

I have read and understand the above require	rements
--	---------

Applicant's Signature/Date


Public Works Department Road Operations Division . Residential Driveway Apron Permit Effective February 2017



DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

RESIDENTIAL DRIVEWAY



1" ASPHALT WITH

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT—OF—WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT—OF—WAY LINE.


& 6" COMPACTED SUBGRADE



DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

RESIDENTIAL DRIVEWAY CONFORMING TO GRADE OR SWALE.



OR

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

& 6" COMPACTED SUBGRADE

^{1&}quot; ASPHALT WITH

^{6&}quot; COMPACTED LIMEROCK BASE