




Residential Driveway Apron Permit Application

(Please Print or Type)



Date: 03/12/18 Bldg Permit No. _____

Dodd McDowell

1482500 / 06 / 18 / 24

Applicant/ Name Permit Will Be Returned To:

Alt. Key# Section Township Range

1020 Lake Sumter Landing

1012 ALOHA WAY LADY LAKE FL 32159

Applicant's Street Address

House Number / Road Name

The Villages, FL 32162

Orange Blossom Gardens / _____

Applicant's City, State, Zip

Subdivision Name

Dodd McDowell

Digitally signed by Dodd McDowell
DN: cn=Dodd McDowell, o=McDowell
Construction, ou,
email=dodd.mcdowell@thevillages.com, c=US
Date: 2018.03.12 10:59:35 -0400

3523919669

Dodd McDowell

Signature of Applicant

Phone Number

Applicant, Please Print Name

tracy.waterman@agewavesolutions.com

CGC1507683

Applicant's e-mail address

Contractor License # (Required unless built by owner)

A driveway permit is required to construct a new driveway, modify an existing driveway to meet county requirements, or install a temporary construction entrance within the public rights-of-way of County maintained roads. Issuance of a driveway permit does not vest any rights to the property owner for zoning, land use changes, or site improvements. The owner must follow all County procedures for permitting.

Driveway must be constructed in accordance with the Lake County Land Development Regulations and as shown on the attached sketch. Applicant holds Lake County harmless from all damages, claims, or injuries which may result from such work. Any deviation from the attached sketch must first be approved in writing by Lake County Public Works Department. Please see attached minimum requirement details for specifications.

Check one:

- Clay Road – No apron required – culvert pipe may be required – sod all disturbed areas.**
- Paved Road – Option 1: 6" limerock base and minimum 1" Type S-III Asphalt. Option 2: 6" reinforced concrete (3000 PSI) using 10 foot square of 6" x 6" wire mesh placed a minimum of 10' from edge of existing pavement. Culvert pipe may be required – Sod all disturbed areas.**

In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% cross slope) in compliance with ADA requirements.

County Road # 7901 **To be completed by County Staff**

Driveway Permit Fee: \$50.00 Check/Transaction #: Credit Card Date: 7/17/18 Fee Code: **PUBSV1**

Permit # 15847 Maint Area: 1 Signed: _____ Date Approved: _____

Permit Shall Expire One (1) Year From Date Approved Date Expired: _____

Date of Final Inspection: _____ Inspector: _____

Comments or special conditions: _____

The design has been reviewed and upon completion should meet the regulations and requirements as noted on this application. The driveway shall be constructed per approved subdivision plans if applicable. For inspection of a driveway associated with a building permit, call Lake County Building Services Division at 352-343-9634. For inspection of a joint (Common Split) driveway or a driveway not associated with a building permit, call Lake County Public Works Department at 352-253-6019. Submit permit to: Lake County Public Works, Post Office Box 7800, Tavares, FL 32778

Public Works Department
Road Operations Division

7/13/18
7/13/18

Residential Driveway Apron Permit
Effective February 2017



Residential Driveway Apron Permit Application Requirements

To be completed by County Staff

- Single Family Driveway (standard A)
- Joint Driveway (Common/Split) (standard B)
- Driveway apron as Swale Check (standard C)
- Piped Driveway apron (standard D)
- Driveway apron conforming to Grade or Swale (standard E)
- Driveway apron with Miami Curb & Gutter (standard M)
- Driveway apron with Standard Curb & Gutter (standard S)

Permit Number

*The applicable driveway apron standard will be included with approved permit that is sent to applicant. *

1. Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness. (See detail on attachment).
2. To conform to sidewalk requirements, subdivision construction plans are available for review in the Lake County Public Works Department located at 323 N. Sinclair Avenue in Tavares.
3. Driveways are not permitted in the radius return of an intersection. With the exception of joint driveways, driveway aprons must be 100 feet from the nearest intersecting road and 10 feet from the nearest property corner. The driveway width at the property line may not exceed 24 feet (10 feet minimum) and shall include either the standard minimum radius of 8 feet or 8 foot long by 4 foot wide flares on either side of the driveway, for a maximum width of 32' at the edge of the roadway. Variance requests should be submitted to the Lake County Public Works Department.
4. Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and/or repair. If pavers are removed to facilitate Lake County and/or a utility company to perform utility installation and/or maintenance, the paver(s) used as replacements may not be able to be matched.
5. If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood. If there are no other culverts in the neighborhood, the culvert pipe shall be a minimum of 15 inches in diameter and a minimum of 30 feet in length measured from the end of miter to the end of miter. All right-of-way must be restored to its original condition and in accordance to applicable Lake County Codes. All disturbed areas must be sodded, matching existing grass type. Applicant shall be responsible for sod until it is established.
6. Driveway apron slope may not exceed 14%. Variance requests should be submitted to the Lake County Public Works Department. In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% cross slope) in compliance with ADA requirements.
7. Driveway permit shall expire one (1) year from date approved.
8. Driveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).

I have read and understand the above requirements _____


Dodd McDowell

Digitally signed by Dodd McDowell
DN: cn=Dodd McDowell, o=McDowell Construction,
ou, email=dodd.mcdowell@thevilleges.com, c=US
Date: 2018.03.12 10:59:54 -0400

Applicant's Signature/Date

Public Works Department
Road Operations Division

Residential Driveway Apron Permit
Effective February 2017



SCREEN ENCLOSURE ENGINEERED SEPARATELY

TOTAL IMPERVIOUS AREA	
TOTAL LOT AREA	6842.88
TOTAL COVERED AREA	2415
PERCENT COVERED	42.3%

COVERED AREA CALCULATIONS (WITHIN PROPERTY LINES)	
HOME AREA	2360
DRIVEWAY AREA	480
SIDEWALK AREA	55
PATIO/PAD AREA	20
SCREEN ENCL AREA	0
TOTAL COVERED AREA	2415

NOTE:
 LOT SQUARE FOOTAGE
 TAKEN FROM-
 LAKE COUNTY PROPERTY
 APPRAISER'S OFFICE
[HTTP://WWW.LAKECOPROPAPPR.COM](http://www.lakecountypappr.com)

TOTAL CONC. SQ FTG. IN EASEMENT: 232 SQ. FT

<p>THE VILLAGES IS A REGISTERED TRADEMARK OF FLS 2ND COMPANY OF THE VILLAGES, INC. ALL RIGHTS RESERVED.</p>	COTTAGE SERIES ABOUT TIME III UNIT & LOT 1-81	SCALE: 1/8"=1'-0" DRAWN BY: TT CHECKED BY: JF SAVE DATE: 3/20/18 11:41 AM PLOT DATE: 3/20/18 11:41 AM	REVISIONS <table border="1"> <thead> <tr> <th>DATE</th> <th>PAGES</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	DATE	PAGES	DESCRIPTION				AREA CALCULATIONS <table border="1"> <thead> <tr> <th>TYPE</th> <th>AREA</th> </tr> </thead> <tbody> <tr> <td>CLIMATE CONTROLLED</td> <td>1358 SF</td> </tr> <tr> <td>GARAGE</td> <td>688 SF</td> </tr> <tr> <td>LANAI</td> <td>227 SF</td> </tr> <tr> <td>ENTRY</td> <td>36 SF</td> </tr> <tr> <td>LANAI</td> <td>30 SF</td> </tr> <tr> <td>TOTAL</td> <td>2259 SF</td> </tr> </tbody> </table>	TYPE	AREA	CLIMATE CONTROLLED	1358 SF	GARAGE	688 SF	LANAI	227 SF	ENTRY	36 SF	LANAI	30 SF	TOTAL	2259 SF	BUILDING OFFICIAL 	<p>340 HEALD WAY, SUITE 812 THE VILLAGES, FLORIDA 32149 PH: (407) 391-9888 FAX: (407) 391-9898 CO#: AG0500718 CO#: 89711 KEVIN L. KATZ, P.E., FLS. LIC. NO. 63119</p>	SITE PLAN <div style="text-align: center; font-size: 2em; font-weight: bold;">1</div>
	DATE	PAGES	DESCRIPTION																								
TYPE	AREA																										
CLIMATE CONTROLLED	1358 SF																										
GARAGE	688 SF																										
LANAI	227 SF																										
ENTRY	36 SF																										
LANAI	30 SF																										
TOTAL	2259 SF																										
STREET: 1012 ALOHA WAY																											
OF 9																											

RECEIPT

LAKE COUNTY BOCC
315 W MAIN ST
Tavares , FL 32778
Phone

Transaction Type : Sale

Comment :

Merchant-Defined Data Fields

Merchant-Defined Data Field 1 : Residential Driveway Apron Permits (11)
Department : Public Works
Merchant-Defined Data Field 3 : 5056260.341213

Total : 555.50 USD

Cardholder Information

Name Randall Thompson
Credit Card Type : MasterCard
Credit Card Number : #####1876

Company : Agewave Solutions, Inc.
Phone : 3523919669
Email : tracy.waterman@agewavesolutions.com

1 of 11