

### Residential Driveway Apron Permit Application

LAKE COM TO			į.	12		4	i e	1	
LAKETOLOGI	1			ì	i		1		
PUPING WO.	-	,		(* ) ( <sub>0,7</sub> )	(				5-

FLORIDA (Please	Print or Type)							
Date: 06/11/18 Bldg Permit No	L Program West							
Dodd McDowell	1672601 ,06 ,18 ,24							
Applicant/ Name Permit Will Be Returned To:	Alt. Key# Section Township Range							
1020 Lake Sumter Landing	912 KIM LN							
Applicant's Street Address	House Number / Road Name							
The Villages, FL 32162 Orange Blossom Gardens								
Applicant's City, State, Zip	Subdivision Name							
Will littly will be supposed by two the based of the base	Dodd McDowell							
Signature of Applicant Phone Number	Applicant, Please Print Name							
tracy.waterman@agewavesolutions.com	CGC1507683							
Applicant's e-mail address	Contractor License # (Required unless built by owner)							
install a temporary construction entrance within the public rights-of-way of County maintained roads. Issuance of a driveway permit does not vest any rights to the property owner for zoning, land use changes, or site improvements. The owner must follow all County procedures for permitting.  Driveway must be constructed in accordance with the Lake County Land Development Regulations and as shown on the attached sketch. Applicant holds Lake County harmless from all damages, claims, or injuries which may result from such work. Any deviation from the attached sketch must first be approved in writing by Lake County Public Works Department. Please see attached minimum requirement details for specifications.  Check one:  Clay Road – No apron required – culvert pipe may be required – sod all disturbed areas.  Paved Road – Option 1: 6" limerock base and minimum 1" Type S-III Asphalt. Option 2: 6"reinforced								
concrete (3000 PSI) using 10 foot square of 6" x 6 pavement. Culvert pipe may be required – Sod all d	" wire mesh placed a minimum of 10' from edge of existing disturbed areas.  Iriveway must include a minimum 4 foot wide path traversing the							
County Road # 8002 To be com	pleted by County Staff							
Driveway Permit Fee: \$50.00 Check/Transaction #:	Crafit lovel Date: 7/11/18 Fee Code: PUBSV1							
Permit # <u>15915</u> Maint Area: <u> </u> Si	gned: Date Approved: 9-18-18							
Permit Shall Expire One (1) Year From Date Approve	d Date Expired: 7/14/19							
Date of Final Inspection: Inspec	ector:							
Comments or special conditions:								
application. The driveway shall be constructed per driveway associated with a building permit, call L inspection of a joint (Common Split) driveway or a d	should meet the regulations and requirements as noted on this approved subdivision plans if applicable. For inspection of a Lake County Building Services Division at 352-343-9634. For Iriveway not associated with a building permit, call Lake County to permit to: Lake County Public Works, Post Office Box 7800,							

Public Works Department Road Operations Division Date 7/3/8 10 1/5/8 Date 0re 7/5/P Residential Driveway Apron Permit Effective February 2017



#### Residential Driveway Apron Permit Application Requirements

To be completed by County Staff							
<ul><li>Single Family Driveway (standard A)</li><li>Joint Driveway (Common/Split) (standard B)</li></ul>	Permit Number						
☐ Driveway apron as Swale Check (standard C) ☐ Piped Driveway apron (standard D) ☐ Driveway apron conforming to Grade or Swale (standard E)							
Driveway apron with Miami Curb & Gutter (standard M) Driveway apron with Standard Curb & Gutter (standard S)							
*The applicable driveway apron standard will be included with approved permit that is sent to applicant. *							

- 1. Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness. (See detail on attachment).
- 2. To conform to sidewalk requirements, subdivision construction plans are available for review in the Lake County Public Works Department located at 323 N. Sinclair Avenue in Tavares.
- 3. Driveways are not permitted in the radius return of an intersection. With the exception of joint driveways, driveway aprons must be 100 feet from the nearest intersecting road and 10 feet from the nearest property corner. The driveway width at the property line may not exceed 24 feet (10 feet minimum) and shall include either the standard minimum radius of 8 feet or 8 foot long by 4 foot wide flares on either side of the driveway, for a maximum width of 32' at the edge of the roadway. Variance requests should be submitted to the Lake County Public Works Department.
- 4. Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and/or repair. If pavers are removed to facilitate Lake County and/or a utility company to perform utility installation and/or maintenance, the paver(s) used as replacements may not be able to be matched.
- 5. If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood. If there are no other culverts in the neighborhood, the culvert pipe shall be a minimum of 15 inches in diameter and a minimum of 30 feet in length measured from the end of miter to the end of miter. All right-of-way must be restored to its original condition and in accordance to applicable Lake County Codes. All disturbed areas must be sodded, matching existing grass type. Applicant shall be responsible for sod until it is established.
- 6. Driveway apron slope may not exceed 14%. Variance requests should be submitted to the Lake County Public Works Department. In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% cross slope) in compliance with ADA requirements.
- 7. Driveway permit shall expire one (1) year from date approved.
- 8. Driveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).

I have read and understand the above requirements

DAY HOPMEN

Digitally signed by Dodd McDowati , OM: cr=Dodd McDowali, o=McDowat Construction, , ow, email=dadd.mcdowali@theklingos.com, c=US Dalòt 2018.08.11 11:38.00 +04/00\*

Applicant's Signature/Date

Public Works Department Road Operations Division


Residential Driveway Apron Permit Effective February 2017



# DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

## RESIDENTIAL DRIVEWAY



1" ASPHALT WITH

A

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE, RIGHT-OF-WAY LINE.

& 6" COMPACTED SUBGRADE




# DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

-

# RESIDENTIAL DRIVEWAY CONFORMING TO GRADE OR SWALE.



OR

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

& 6" COMPACTED SUBGRADE

<sup>1&</sup>quot; ASPHALT WITH

<sup>6&</sup>quot; COMPACTED LIMEROCK BASE

<sup>&</sup>amp; 12" COMPACTED SUBGRADE