




Residential Driveway Apron Permit Application (Please Print or Type)

MAR 21 2018



Date: 3/21/18 Bldg Permit No. 2018020800

Strain, William Applicant/ Name Permit Will Be Returned To:

2621 Sunrise BV Applicant's Street Address

Mount Dora FL 32957 Applicant's City, State, Zip

Mission Park 813-992-23 Signature of Applicant Phone Number

3808899 Alt. Key# Section Township Range

2621 Sunrise Blvd. House Number / Road Name

Dora Pines Subdivision Name

Jacob Hancock Applicant, Please Print Name

FH 115041 Contractor License # (Required unless built by owner)

Applicant's e-mail address

A driveway permit is required to construct a new driveway, modify an existing driveway to meet county requirements, or install a temporary construction entrance within the public rights-of-way of County maintained roads. Issuance of a driveway permit does not vest any rights to the property owner for zoning, land use changes, or site improvements. The owner must follow all County procedures for permitting.

Driveway must be constructed in accordance with the Lake County Land Development Regulations and as shown on the attached sketch. Applicant holds Lake County harmless from all damages, claims, or injuries which may result from such work. Any deviation from the attached sketch must first be approved in writing by Lake County Public Works Department. Please see attached minimum requirement details for specifications.

Check one:

- Clay Road - No apron required - culvert pipe may be required - sod all disturbed areas.
Paved Road - Option 1: 6" limestone base and minimum 1" Type S-XII Asphalt. Option 2: 6" reinforced concrete (3000 PSI) using 10 foot square of 6" x 6" wire mesh placed a minimum of 10' from edge of existing pavement. Culvert pipe may be required - Sod all disturbed areas.

In areas where sidewalks are present or planned, the driveway must include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1.5% cross slope) in compliance with ADA requirements.

County Road # 4680 To be completed by County Staff
Driveway Permit Fee: \$30.00 Check/Transaction #: S9059 Date: 3/21/18 Fee Code: PUBSV1
Permit # 15926 Maint Area: 3 Signed: [Signature] Date Approved: 2/20/18
Permit Shall Expire One (1) Year From Date Approved Date Expired: 2/20/19
Date of Final Inspection: Inspector:
Comments or special conditions:

The design has been reviewed and upon completion should meet the regulations and requirements as noted on this application. The driveway shall be constructed per approved subdivision plans if applicable. For inspection, call Lake County Building Services Division at 352-343-9634. For joint (Common Split) driveway inspection, call Lake County Public Works Department at 352-253-6019. Submit permit to: Lake County Public Works, Post Office Box 7800, Tavares, FL 32778

Public Works Department Road Operations Division

Residential Driveway Apron Permit Effective June 2015

Table with 2 columns: Action/Item, Date. Rows include Entered Data One (7/3/18), First Scan (7/3/18), Updated Data One (8/22/18), Second Scan (8/22/18), and Client (8/30/18).



Residential Driveway Apron Permit Application Requirements

To be completed by County Staff

- Single Family Driveway (standard A)
Joint Driveway (Common/Split) (standard B)
Driveway apron as Swale Check (standard C)
Piped Driveway apron (standard D)
Driveway apron conforming to Grade or Swale (standard E)
Driveway apron with Miami Curb & Gutter (standard M)
Driveway apron with Standard Curb & Gutter (standard S)

2018000800
Permit Number

The applicable driveway apron standard will be included with approved permit that is sent to applicant.

- 1. Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness.
2. To conform to sidewalk requirements, subdivision construction plans are available for review in the Lake County Public Works Department located at 323 N. Sinclair Avenue in Tavares.
3. Driveways are not permitted in the radius return of an intersection. Driveway aprons must be 100 feet from the nearest intersecting road and may not exceed 24 feet in width at the edge of the roadway.
4. Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and/or repair.
5. If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood.
6. Driveway apron slope may not exceed 14%.
7. Driveway permit shall expire one (1) year from date approved.
8. Driveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).

I have read and understand the above requirements

Melissa Park
Applicant's Signature/Date

Public Works Department
Road Operations Division


Residential Driveway Apron Permit
Effective June 2015



DEPARTMENT OF PUBLIC WORKS
ENGINEERING DIVISION
437 ARDICE AVE.
EUSTIS, FLORIDA 32726

A

RESIDENTIAL DRIVEWAY



* SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT-OF-WAY LINE.

1" ASPHALT WITH
6" COMPACTED LIMEROCK BASE
& 12" COMPACTED SUBGRADE

OR


6" 3,000 PSI CONCRETE
REINFORCED WITH 10-10x6"x6" MESH
& 6" COMPACTED SUBGRADE



DEPARTMENT OF PUBLIC WORKS
ENGINEERING DIVISION
437 ARDICE AVE.
EUSTIS, FLORIDA 32726

E

RESIDENTIAL DRIVEWAY CONFORMING TO GRADE OR SWALE.



* SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT-OF-WAY LINE.

1" ASPHALT WITH
6" COMPACTED LIMEROCK BASE
& 12" COMPACTED SUBGRADE

OR

6" 3,000 PSI CONCRETE
REINFORCED WITH 10-10x6"x6" MESH
& 6" COMPACTED SUBGRADE