

Residential Driveway Apron Permit Application (Please Print or Type)

Date:	Bldg Permit No. 0 1 8	80 Z 0 0 2 5 JUL U 2 2018
Konald t	t. Thomas Na	19245700019 15 1235 25E
	nit Will Be Returned To:	7 2Alb Key Coo Section Township Range
	slo .	XXX Groveland Farms Rd
Applicant's Street Add	/	House Number / Road Name
Applicant's City, State,		Groveland Farms, PB21PG
· · · · · · · · · · · · · · · · · · ·		Subdivision Name
Signature of Applicant	3526360540 Phone Number	- 15/1 WICK 111 1.1 (UIT) (A.
thomacuttlege		Applicant, Please Print Name
Applicant's e-mail addr	ess	Contractor License # (Required unless built by owner)
A driveway permit is rec	Julied to construct a new drivews:	
install a temporary consti permit does not vest any follow all County procedu	ruction entrance within the public rights to the property owner for zires for permitting.	y, modify an existing driveway to meet county requirements, or ights-of-way of County maintained roads. Issuance of a driveway coning, land use changes, or site improvements. The owner must
Driveway must be const	gisted in account on the first	·
WORK. Any deviation from	int hölds Lake County harmless from the attached sketch must first be num requirement details for specific	ce County Land Development Regulations and as shown on the om all damages, claims, or injuries which may result from such e approved in writing by Lake County Public Works Department.
Clay Road - No and	on required - culvert pipe may	/ be required – sod all disturbed areas.
concrete (3000 PST) us	ing 10 foot gappes of Cli - an	""" Type S-III Asphalt. Option 2: 6"reinforced
•		The state of the s
In areas where sidewalks driveway apron (at a maxi	are present or planned, the drive mum 1.5% cross slope) in complian	eway must include a minimum 4 foot wide path traversing the ice with ADA requirements.
County Road # 1023	To be comple	ted by County Staff
Driveway Permit Fee: \$	50.00 Check/Transaction#: 54	
Permit#16077		Tee Code: PUBSV1
	organe	Date Approved: 8-28-8
	(1) Year From Date Approved	Date Expired: 8/23/19
Date of Final Inspection:	Inspector	
Comments or special condit	ions: MUST HAVE AS OF GROVELAND F	ARMS RD. TO PROPERTY LINE
The design has been revi	ewed and nnon completion shor	
County Building Services Public Works Department	Division at 352-343-9634. For j	uld meet the regulations and requirements as noted on this yed subdivision plans if applicable. For inspection, call Lake oint (Common Split) driveway inspection, call Lake County
Submit permit to: Lake Co	ounty Public Works, Post Offic	e Box 7800, Tavares, FL 32778
Public Works Department		
Road Operations Division	Filtered Da ta One	Residential Driveway Apron Permit \$\frac{1}{2\lambda_{15}}\$
	st Scan	8/12/8
	es et nis se	1/24/18
		2/24/18



Residential Driveway Apron Permit Application Regultements

1	Taylor Taylor Sphicarol Requirements			
	To be completed by County Staff	4400		
	Single Family Driveway (standard A) Joint Driveway (Common/Split) (standard B) Permit Number	, sol		
	Driveway apron as Swale Check (standard C) Piped Driveway apron (standard D) Driveway apron conforming to Grade or Swale (standard E)			
77.0	Driveway apron with Miami Curb & Gutter (standard M) Driveway apron with Standard Curb & Gutter (standard S)			
<u> </u>	applicable driveway apron standard will be included with approved permit that is sent to applicant,	淋		
1.	Sidewalks must be constructed per FDOT Index 310, with maximum cross slope of 1.5%, 6 inches minimum thickness. (See detail on attachment).	3		
2.	To conform to sidewalk requirements, subdivision construction plans are available for review in take County Public Works Department located at 323 N. Sinclair Avenue in Tavares.			
. 3,	Driveways are not permitted in the radius return of an intersection. Driveway aprons must be a feet from the nearest intersecting road and may not exceed 24 feet in width at the edge of the roadway. Variance requests should be submitted to the Lake County Public Works Department.	the		
4.	Pavers installed as a driveway apron are the resident's responsibility to maintain, replace and repair. If pavers are removed to facilitate Lake County and/or a utility company to perform util installation and/or maintenance, the paver(s) used as replacements may not be able to be matched.	lity d.		
5.	If a culvert pipe is required, it shall be the same diameter of existing culverts in neighborhood, there are no other culverts in the neighborhood, the culvert pipe shall be a minimum of 15 inches diameter and a minimum of 30 feet in length measured from the end of miter to the end of miter of way must be restored to its original condition and in accordance to applicable La County Codes. All disturbed areas must be sodded, matching existing grass type. Applicant shall be responsible for sod until it is established.	in er		
6.	Driveway apron slope may not exceed 14%. Variance requests should be submitted to the Lal County Public Works Department. In areas where sidewalks are present or planned, the drivewant include a minimum 4 foot wide path traversing the driveway apron (at a maximum 1,5% croslope) in compliance with ADA requirements.			
7.	Oriveway permit shall expire one (1) year from date approved.			
3.	Oriveway Apron Permit Application shall include a check made payable to the Lake County Board of County Commissioners (BOCC).	ı		
I have read and understand the above requirements				
	Applicant's Signature/Date			

Public Works Department Road Operations Division


Residential Drivoway Apron Permit Effective June 2015



DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

RESIDENTIAL DRIVEWAY



OR

1" ASPHALT WITH

A

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS

SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE, RIGHT-OF-WAY LINE.


& 6" COMPACTED SUBGRADE



DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION

437 ARDICE AVE. EUSTIS, FLORIDA 32726

PIPED RESIDENTIAL DRIVEWAY



1" ASPHALT WITH

D

6" COMPACTED LIMEROCK BASE

& 12" COMPACTED SUBGRADE

6" 3,000 PSI CONCRETE

REINFORCED WITH 10-10x6"x6" MESH

SIDEWALK (IF REQUIRED) SHALL BE CONSTRUCTED TO MEET FDOT INDEX 310, ADA SPECIFICATIONS SPECIFICATIONS FOR PUBLIC RIGHT-OF-WAYS, AND LAKE COUNTY STANDARDS WITH A MAXIMUM CROSS SLOPE OF 1.5% AND A MAXIMUM RUNNING GRADE SLOPE OF 5%, OFFSET 1' FROM PROPERTY LINE/ RIGHT-OF-WAY LINE.

& 6" COMPACTED SUBGRADE