

New 16 FT Big Tex Dump Trailer

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the furnishing, off-loading and delivery of a new Sixteen (16) FT Dump Trailer (**Big Tex**) or **approved equal** for the Lake County Water Authority. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- See attached photo for reference
- Sixteen (16) FT Long X Seven (7) FT wide Dump Trailer
- **14 LP-P4 Big Tex or approved equal.**
- 14,000 LB GVWR, fifteen (15) cubic yards. Scissor lift
- 7 FT slide in ramps, combo gate, powder coated (black), recessed LED lights, Lippert Axles, Radial tires, lockable pump & battery box
- Ten (10) gauge steel floor
- Number of axles- two (2)
- **Price includes delivery to Lake County Water Authority – 27351 State Road # 19, Tavares, FL 32778**

1.02 SUBMITTALS:

- A. Submit product data/specification to the LCWA (Lake County Water Authority) for review and approval of all items of work if requested.
- B. Equipment shall be inspected by the County for damage and chipped or marred finish. Contractor shall replace any damaged or rejected products at no conditional cost to the owner. The owner's representative may authorize acceptance of chipped or scratched painted surfaces repaired / replaced by the contractor at his own risk.

