

**EXHIBIT A – SCOPE OF WORK
INSTALLATION OF FIELD FENCE AT NEIGHBORHOOD LAKES SCENIC TRAIL &
TRAILHEAD**

1. CONTRACTOR RESPONSIBILITIES

Contractor shall:

- 1.1 Be fully competent in all aspects of the installation of field fence in a safe manner.
- 1.2 Furnish all labor, materials, equipment, fuel and any other incidental costs, and supervision necessary for the installation of 6,400 linear feet of woven wire field fence at Neighborhood Lakes Scenic Trail & Trailhead, 26656 CR46A, Mount Plymouth, FL 32776.
- 1.3 Be responsible for damages caused as the result of completing the project.
- 1.4 Furnish all tools and equipment to complete project timely and efficiently.
- 1.5 Ensure all equipment used is in safe working order and is properly maintained.
- 1.6 Contractor may use on-site storage area to store equipment, however, it shall be used at the Contractors own risk. No paint, materials or equipment shall be stored within the buildings.
- 1.7 Final location to be approved by the Office of Parks & Trails.
- 1.8 All work and materials are subject to the approval of the County.
- 1.9 Contractor shall clean-up, remove, and dispose of all debris associated with the work performed.
- 1.10 Be responsible for non-performance liquidated damages.
- 1.11 Acceptance: The County will inspect finished product to determine compliance prior to final acceptance of the work.
- 1.12 FIELD CONDITIONS: Verify and coordinate all work to field locations and dimensions.
Contractor is responsible for the installation of temporary construction fencing and signage to safely enclose the work area.
- 1.13 Coordinate all work with Shane Strew (352)516-4916, 48 hours prior to delivery & installation to Neighborhood Lakes Trailhead.

2. SCOPE OF WORK

2.1 Installation of 4-foot-high woven wire field fence

- 2.1.1 Installation of 6,400 linear feet of 4-foot-high woven wire field fence.
- 2.1.2 Install field fence to follow existing fence along property line. (See attached map, diagrams, and photos). Existing fence posts can be used where available.
- 2.1.3 Post spacing shall be every 10 feet.
- 2.1.4 Line posts shall be 3.5 - 4 inches in diameter by 6.5 feet long.
- 2.1.5 Corner and end posts shall be 6 to 8 inches in diameter by 8 feet long.
- 2.1.6 All terminal (corner and end posts) to be set in mixed concrete foundation.
- 2.1.7 Top rail shall be 1"x6"x16' pressure treated fence boards.
- 2.1.8 Proper corner and end bracing to be utilized.
- 2.1.9 Mesh to be placed towards the inside of the park property.
- 2.1.10 Any necessary trimming and disposal of trees / vegetation is the responsibility of the contractor prior to fence installation.


3. COUNTY RESPONSIBILITIES

- 3.1 County staff will meet with contractor to coordinate necessary vegetation removal and final fence locations.
- 3.2 A site meeting can be set up prior to the response due date by the County if necessary.



October 25, 2021

1:7,500



- | | | | |
|---|-------------------------|---|---------------------------|
| — | Street Names | □ | Tax Parcels Alternate Key |
| — | Local Streets | □ | Tax Parcels |
| — | Subdivision Lot Numbers | □ | County Boundary |
| □ | Building Footprints | □ | Surrounding Counties |
| □ | Property Name | | |

Lake County Property Appraiser
Lake BCC

