

Resurfacing Basketball, Pickleball & Tennis Court at Astor Lions Park

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to repair any cracks, machine sand surfaces, apply two (2) coats of acrylic re-surfacer, apply two (2) coats latex acrylic color & restripe the basketball court, tennis court & pickleball court (new posts and net required on pickleball court) at Astor Lions Park- 54835 Alco Rd. Astor, FL 32102. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- Field verification by Contractor is recommended.
- Machine sand all surfaces, repair holes & foundation using patch mix to level up to existing surface.
- Crack repair on all cracks using crack filler or other approved product.
- Pull down bad seams with surfacer before coating system starts.
- Apply two (2) coats with acrylic re-surfacer over entire slab with heavy sand.
- Apply two (2) coats of latex acrylic color with sand over entire slab.
- Re-stripe courts to regulation specifications.
- **Must submit color sample for approval.**
- **Pickleball courts require new posts & net they must match pickleball amenities at Pear Park- 26701 US Hwy # 27 Leesburg, FL 34748**

1.02 SUBMITTALS:

- A. All paint submittals to be approved by the office of parks and Trails prior to contractor delivering materials to site.

1.03 FIELD CONDITIONS: Verify and coordinate all work to field locations and dimensions. Contractor is responsible for the installation of temporary construction fencing and signage to safely enclose the work area.

1.04 WORKMANSHIP:

- A. All furnishings described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.

1.05 ACCEPTANCE

- A. The County will review each installation to determine compliance prior to final acceptance of the work.

1.06 CLEANING

- A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, soil, debris, equipment and grade the existing work area.







