

**EXHIBIT A – SCOPE OF WORK
REMOVE AND RELOCATE EXISTING FENCE AT EAST LAKE SPORTS &
COMMUNITY COMPLEX**

1. CONTRACTOR RESPONSIBILITIES

Contractor shall:

- 1.1 Be fully competent in all aspects of the removal and installation of chain link fence in a safe manner.
- 1.2 Furnish all labor, materials, equipment, fuel and any other incidental costs, and supervision necessary for the relocation of 260 feet of existing 14-foot-high chain link fence at East Lake Sports & Community Complex, 24809 Wallick Road, Sorrento, FL 32776.
- 1.3 Be responsible for non-performance liquidated damages.
- 1.4 Be responsible for damages caused as the result of completing the project.
- 1.5 Furnish all tools and equipment to complete project timely and efficiently.
- 1.6 Ensure all equipment used is in safe working order and is properly maintained.
- 1.7 Contractor may use on-site storage area to store equipment, however, it shall be used at the Contractors own risk. No paint, materials or equipment shall be stored within the buildings.
- 1.8 All work and materials are subject to the approval of the County.
- 1.9 Contractor shall clean-up, remove, and dispose of all debris associated with the work performed.
- 1.10 Acceptance: The County will inspect finished product to determine compliance prior to final acceptance of the work.
- 1.11 FIELD CONDITIONS: Verify and coordinate all work to field locations and dimensions. Contractor is responsible for the installation of temporary construction fencing and signage to safely enclose the work area.
- 1.12 Coordinate all work with Shane Strew (352)516-4916, 48 hours prior to delivery & installation to East Lake Sports & Community Complex.

2. SCOPE OF WORK

2.1 Removal and relocation of existing 14-foot-high black vinyl coated chain link fence

- 2.1.1 Remove 260 linear feet of 14-foot-high black vinyl coated chain link fence.
- 2.1.2 Re-install fence approximately 1 foot off existing galvanized chain link fence of neighboring property. (See attached map and photos for location).
- 2.1.3 To the west side, gap created by moving fence needs to be closed in with a section of 14-foot-high chain link fence to match existing.
- 2.1.4 To the east side, gap created by moving fence needs to be closed in with a section of 8-foot-high chain link fence to match existing 8-foot-high fence which currently runs north to south. (See attached pictures).
- 2.1.5 Post spacing to remain 10 feet.
- 2.1.6 Line posts are 3 inches in diameter.
- 2.1.7 Corner and end posts are 4 inches in diameter.
- 2.1.8 All terminal and line post to be set in mixed concrete foundation size of 12 inches in diameter by 42 inches deep. (This is the minimum being required).
- 2.1.9 Top rail, upper and lower middle rails are 1 5/8 inches in diameter.
- 2.1.10 Bottom rail is 1 5/8 inches in diameter.
- 2.1.11 Depth of posts into ground/footer is 4 feet. (Line, end, gate, and corner posts).
- 2.1.12 Horizontal braces at corner and end posts are 2 @ 1 5/8 inches.
- 2.1.13 Diagonal braces are ½ inch in diameter.

EXHIBIT A – SCOPE OF WORK

RELOCATION OF FENCE AT EAST LAKE SPORTS & COMMUNITY COMPLEX

- 2.1.16 All hardware shall be painted black to ensure a uniform finish.
- 2.1.17 All bolts shall be cut back to a finished length of less than 3 threads exposed.
- 2.1.18 Any necessary trimming and disposal of trees / vegetation is the responsibility of the contractor after fence is removed and before re-installation.

3. COUNTY RESPONSIBILITIES

- 3.1 The County will provide a storage area for the Contractor to store equipment. The County is not responsible for theft of the Contractor's items.

[The remainder of this page intentionally left blank]

East Lake Sports & Community Complex



TOTAL ACRES: 75

SITE DIRECTORY

P Parking
W Multi-Use Trail

W Restroom
E Exercise Station

P Pavilion
P Playground

C Concession
B Batting Cages

S Storage
D Dog Park

F Fire Station
L Library



