

Contractor shall provide a quote to remove and replace approx. 3,500 LF of field fence at a parcel owned by Lake County. There are two gates located on the property that will not require replacement. All vegetation will be cleared by County staff prior to commencement of work. Contractor may utilize metal t-posts in-lieu of 4-5" CCA treated wood fence posts, provide that wood post bracing is sufficient to support tension of wire. All corners and gate posts shall be wood posts with 7-8" diameter CCA treated wood fence posts and high tensile wire bracing. Fence post spacing shall not exceed 10' OC. Existing gates can be reused. Contractor shall exercise caution not to damage the guardrail between the roadway and property line on French Rd and Lake Griffin Rd. All existing fencing material shall be removed from the site by the contractor.