

REQUEST FOR QUOTES (RFQ)

OPEN MARKET

WATER TANK REMOVAL AND DISPOSAL AT PINE LAKES CONVENIENCE CENTER

LOCATION:

Pine Forest Park (aka Pine Lakes Solid Waste Convenience Center) 32520 State Road 44, Deland, Florida 32720.

QUOTES DUE:

Tuesday, March 31st

SITE VISIT:

Monday, March 16th at 10:30 AM

SCOPE OF WORK:

A "qualified licensed contractor" (hereinafter "Contractor") shall furnish all labor, materials, equipment, components/devices, transportation, fuel, supervision, permits, inspections and all other incidentals necessary to complete all necessary work, all in accordance with all parts of this solicitation to obtain all permits, licenses, certificates, or any required approvals of plans or specifications as may be required by federal, state, and local laws, ordinances, rules and regulations for the proper execution, removal, and legal disposal of the 25,000 gallon water tank and associated piping located at the Lake County Pine Forest Park, 32520 State Road 44, Deland, Florida 32720.

CONTRACTOR REQUIREMENTS

- 1.1 The Contractor shall be properly licensed and comply with all Federal, State, County, and local regulations in demolition(s), tank removal and disposal, including the proper removal and disposal of any related hazardous materials.
- 1.2 The Contractor shall provide flagman for traffic control and safety at any time the demolition requires the blocking of any road, highway and/or

rights-of-way. This shall include the loading or unloading of heavy equipment.

- 1.3 The Contractor shall provide perimeter security fencing that shall prevent trespass during demolition operations, overnight hours, and non-operating days for the duration of the work.
- 1.4 The Contractor shall excavate, remove and properly dispose of the 25,000 gallon water tank and associated piping and valves. All pricing shall be for the complete turn-key project. In the event that conditions are encountered in the field that were not identified in the scope of work, the Lake County Construction Program Manager shall be notified immediately.
- 1.5 The Contractor shall remove and properly disposal of all debris including, but not limited to, cuttings, tank or piping fragments/pieces, fallen trees or brush, garbage, discarded metal, glass, and wood products.
- 1.6 The Contractor shall backfill the excavated area with clean fill dirt.
- 1.7 The Contractor shall sod the exposed dirt area with Bahia sod.
- 1.8 The Contractor may salvage or recycle materials. Recycling of any property shall be the privilege of the Contractor. If the material is not salvageable, it must be properly disposed of at a State Permitted landfill.
- 1.9 The Contractor shall maintain the area free of accumulation of waste materials and other debris resulting from the tank excavation.
- 1.10 The Contractor shall submit notification within 10 working days of demolition/tank removal activities to the Florida Department of Environmental Protection's Central District Office or at the Florida Department of Environmental Protection's submit notice web link (www.fldepportal.com/go/submit-registration/), if needed. Provide verification of notification to the Lake County Construction Program Manager prior to the commencement of work.
- 1.11 The Contractor shall be responsible for the safety of the methods employed in the performance of the work. The Contractor shall comply with the regulations set forth by federal, state, and local laws, rules and regulations concerning Occupational Safety and Health Administration (OSHA) and all applicable state labor laws, regulations and standards.
- 1.12 The Contractor shall be responsible for the repair of damage to adjacent buildings, the existing water line, or other property that are damaged as a result of Contractor's work.
- 1.13 The Contractor shall complete work within 30 calendar days from issuance of the Notice to Proceed.

1.14 The Contractor shall submit a detailed summary report of all work completed for this project including pre-job submittals, copies of any applicable permits, Florida Department of Environmental Protection (FDEP) notifications, and post-job submittals to the Lake County Construction Program Manager prior to the submittal of the final payment application.

SUPPORTING DOCUMENTS:

Supporting documents are listed below and incorporated herein as part of the solicitation. Please ensure these documents are reviewed in detail prior to submitting a response to this Request for Quotes.

- Aerial Map of Location
- Photos of Tank