



REAL FLORIDA • REAL CLOSE
Office of Procurement Services

P.O. Box 7800 • 315 W. Main St., Suite 441 • Tavares, FL 32778

SOLICITATION: Name

11/23/2022

Vendors are responsible for the receipt and acknowledgement of all addenda to a solicitation. Confirm acknowledgement by including an electronically completed copy of this addendum with submittal. Failure to acknowledge each addendum may prevent the submittal from being considered for award.

THIS ADDENDUM DOES NOT CHANGE THE DATE FOR RECEIPT OF PROPOSALS.

QUESTIONS/RESPONSES

Q1. The plans say posts spaced 10 foot apart, and 1 x 6 x 16 foot rails. The posts would need to be spaced 8 feet apart in order for the rails to work. Please clarify this. Thank you.

R1. Yes, posts should be spaced 8 feet apart due to the specified top railing dimensions. The existing 2,700 feet of 4-wire fence that runs east to west (please see map) currently has some posts that are set at 14 foot spacing on average. We will need the contractor to set a 3.5 to 4 inch diameter post between each existing post prior to installing field fence. Each post shall be spaced at maximum of 8 feet to support the 16 foot fence boards.

Q2. Can we use an equal to the wire that is in the specs. Red brand is just a label, and all other field fence in that spec will match the spec of the label Red Brand.

R2. An approved equal will be fine, as long as the specifications are the same.

Q3. Is there any way the vegetation could be pushed into the wooded area and left to eventually rot and disappear? Most of the job is light clearing and will require very little clearing if any. But some of the job is heavily wooded and will moderately affect our quote? Either way is fine just asking.

R3. The County can coordinate with the contractor to identify 2 to 3 areas where any significant vegetation can be piled and will later be picked up by County staff.

Q4. The 30-day deadline is a very short period for 6400 feet of fence. 60 or 90 days is more in line with that size job. The scope mentioned liquidated damages, so if 30 days is mandatory, what would the liquidated damages be, and we can figure it into our quote. We are a big company, with 12 crews, but that's an aggressive time frame for a job that size.

R4. The County is willing to extend the 30 day deadline for completion to 60 days.

ADDITIONAL INFORMATION

N/A

The existing 2,700 feet of 4-wire fence that runs east to west (please see map) currently has some posts that are set at 14 foot spacing on average. We will need the contractor to set a 3.5 to 4 inch diameter post between each existing post prior to installing field fence. Each post shall be spaced at minimum of 8 feet to support the 16 foot fence boards.

ACKNOWLEDGEMENT

Firm Name: Click or tap here to enter text.

I hereby certify that my electronic signature has the same legal effect as if made under oath; that I am an authorized representative of this vendor and/or empowered to execute this submittal on behalf of the vendor.

Signature of Legal Representative Submitting this Bid: Click or tap here to enter text.

Date: Click or tap to enter a date.

Print Name: Click or tap here to enter text.

Title: Click or tap here to enter text.

Primary E-mail Address: Click or tap here to enter text.

Secondary E-mail Address: Click or tap here to enter text.